

Schedule of Quantities

**Name of Work: Renovation of Sagarmala Office in PTI Building, New Delhi.**

Sr. No.	Particular	Qty	Unit	Rate	Total Amount
1	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.				
1.1	One Coat	210.00	Sqm		
3	Providing and fixing real wood flooring /skirting of approved make colour, texture and finish. The flooring shall be fixed with plank locking system, with underlayment of 2mm thick foam sheets having density 40kg/cum, over prepared surface with necessary quarter round planks of required size and door reducer of required size wherever required all complete as per direction of Engineer-in-charge	75.00	Sqm		
3	Melamine polishing one or more coat on wood work applying one or more coat melamine with manual to the required colour or shade with matt/glossy finish including surface preparation with putty and sealer filler and primer etc. complete as per direction of Engineer-in-charge.	20.00	Sqm		
4	Cleaning of window glass, partition, floor tiles wall tile wooden almirah with chemical and other powder complete.	500.00	Sqm		
5	Fixing of 10 kv UPS Syatem IIIrd floor in PTI Building.				
5.1	Electrician	3.00	each		
6	Providing and fixing of three Phase Electricity C.T. Meter with load up to 100 kw of approved make with box complete	1.00	each		
7	Providing and fixing C.P. brass push cock approved quality.	2.00	each		
8	Providing and fixing C.P. brass basin Elbow knob type faucet of approved quality.	2.00	each		
9	Providing and fixing 1/2" Granite Stone patti over Wash Basin Counter with moulding complete.	1.00	L.S.		
10	Providing and fixing 18mm thick commercial block board of approved make like Duro century or equivalent for cupboard/cabinet (Shelves shutters and drawers) including necessary clealts. Nauls. Screws & adhesive etc. complete as specification and direction engg. in charge.	4.00	Sqm		

11	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt / suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality.				
11.1	1.0 mm thick.	2.00	Sqm		
12	Providing and fixing required fitting for under basin counter cupboard.	1.00	L.S.		
13	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
13.1	Two or more coats on new work.	5.00	Sqm		
				<b>Total</b>	
				<b>GST @ 18%</b>	
				<b>Total</b>	